Timberlane Regional School District Invitation for Bid Sanitary Waste Disposal Leach Bed #4

Bids Due: Friday, June 22, 2018 10:00AM

Addressed to : Superintendent of Schools 30 Greenough Rd. Plaistow, NH 03865 IFB: Sanitary Waste Disposal Leach Bed #4

A <u>Mandatory</u> Pre-Bid Meeting will be held on **Wednesday**, **June 20, 2018 at 10:00** AM at Timberlane Regional High School – please check in main office.

As-Built Drawings can be accessed by using the following link: goo.gl/aMLcBx

All questions regarding this IFB must be addressed via email to: Thomas.Geary@SAU55.net

Install Effluent Disposal Leaching Bed shown as Future Bed #4 on plan dated 1-2-09 by Civil Construction Management, Inc. and approved by NHDES as CA2009095968. The plan will be updated, revised, resubmitted and approved by NHDES to change the word "Future" to "Proposed".

Contractor shall provide and install Enviro-Septic Leaching Pipes, 18 rows at 90 feet each.

Work is to include excavating, provide and install an 18-outlet distribution box, and about 200 feet of 4-inch SDR 35 PVC pipe and fittings to connect from the box to each row and for venting at the end of each row. Also, provide and install about 240 feet of SDR 35 PVC pipe and fittings to connect from the vents at the end of each row to a riser above ground behind the existing small block building.

To excavate, provide, install and backfill 280 feet of gravity 6-inch SDR 35 PVC pipe from the existing manhole to the distribution box.

To provide and install a 6-inch control gate valve (by VALTERRA or approved equal) installed on the inlet of the pipe at the manhole.

Contractor shall provide and install isolation valves or on all four effluent lines.

The work area is in a field behind the school. Work will require stripping topsoil, excavate and install the leaching bed and all piping, inspections by the Town and State, backfill to grade, spread topsoil, fine grade and hydro-seed all disturbed areas using seed mixture specified by the School. All work to be conducted under the direct supervision of an installer licensed by the State of NH DES